


No. 9195



REGISTRATION EXAMINATION, JUNE 2018  
**CERTIFYING PLUMBER**


**ANSWER SCHEDULE**


## ANSWER 1


- (a) The supervisee must be able to be seen or heard by their supervisor at all times. (2 marks)
- (b) Trainee Limited Certificate (Apprentice)  
Exemption holder (1 mark)
- (c) Trainee – 12 months  
Exemption holder – 24 months (1 mark)
- (d) Certifying Plumber  
Tradesman Plumber (2 marks)

**Total 6 marks**


## ANSWER 2

- (a)  (1 mark)

- (b)  (1 mark)


- (c)  (1 mark)

(d)



(1 mark)

(e)



(1 mark)

**Total 5 marks**

### ANSWER 3

- (a) A 56 kPa
- B 100 kPa
- C 157 kPa

(3 marks)

- (b) (i) Two tanks separated by three floors shown. (1 mark)
- (ii) Inlet to each break tank shown correctly. (1 mark)
- Outlet from each break tank shown correctly. (1 mark)
- Section of vertical pipework between inlet and outlet for each break tank shown removed. (1 mark)

(4 marks)

**Total 7 marks**

## ANSWER 4

- (a) (i) 115 kPa  
(ii) 88 kPa  
(iii) 74 kPa (3 marks)

- (b) 40 mm (1 mark)

- (c) Any FOUR (½ mark for type, 1 mark for highest hazard rating each)

Type of valve	Highest hazard rating
Reduced pressure zone device	High
Double check valve assembly	Medium
Pressure type vacuum breaker	High
Atmospheric vacuum breaker	High

(6 marks)

- (d) (i) 64 mm (1 mark)

- (ii) The float valve outlet and the soffit of the tank overflow.

(2 marks)

**Total 13 marks**

## ANSWER 5

- (a) Any FOUR (½ mark each)
- Number of people in the home
  - Collector area
  - Collector type
  - Thermostat setting
  - Environmental factors (climate)
  - Variable usage
  - Direction of the collector
  - Tilt of the collector
  - Shade
  - Distance from collector to storage unit
  - Roof structure
  - Access for maintenance.
- (2 marks)

- (b) (i) Series or Parallel (1 mark)
- (ii) Correct location of panel inlets. (1 mark)  
 Correct location of panel outlets. (1 mark)  
 Panels are connected consistently with type of system. (1 mark) (3 marks)
- (iii) Parallel  
 Panels are less likely to overheat.  
 Additional panels can be joined to the system more easily.
- Series  
 Higher temperatures achievable  
 Less pipework. (2 marks)
- (c) The latitude of the installation. (1 mark)

**Total 9 marks**

## ANSWER 6

### If fixtures discharging to ORG – sized and vented correctly

Kitchen sink 40 mm no vent  
 Scullery to ORG 40 mm needs vent  
 Scullery to ORG 65 mm no vent req

### Venting

Main vent 50 mm diameter  
 Main vent location

### Fixtures to FWG if used

FWG receiving fixtures from another room (minus 3)  
 FWG receiving waste from kitchen sink/toilet (minus 3)  
 Fixture discharge pipes to FWG incorrect size (minus 1, max 3)

### Main and branches

Main drain not 100 mm  
 Branch drains not 65 mm

Drainage plan altered (minus 9)  
 Missed fixtures (minus 1 each)

**Total 9 marks**

## ANSWER 7

(a)

Fixture	Minimum Pipe Diameter
Basin	32 mm
Domestic kitchen sink with waste disposal	40 mm
Floor waste gully	50 mm
Drinking fountain	25 mm

(2 marks)

(b) Minimum gradient is  $1.65\% = 1:60$  (1 mark)

Fall required =  $6 \div 60 = 0.1 \text{ m} = 100 \text{ mm}$  (1 mark)

(2 marks)

**Total 4 marks**

## ANSWER 8

(a) Any SIX (1 mark each)

- Roofing
- Pipe lagging
- Cladding
- Insulation
- Decorative ceilings
- Soffits
- Flues
- Boilers
- Pipes
- Flooring

(3 marks)

(b) Friable

Non friable

(2 marks)

(c) Any TWO (1 mark each)

Loud noises

Chemicals

Bacteria

Silica dust

Lead

(2 marks)

**Total 7 marks**

## ANSWER 9

(a) Any THREE (1 mark each)

Directors

Shareholders

Board Members

Partners

Chief Executive

Owners

Self employed people

(3 marks)

(b) Any THREE (1 mark each)

Construction work with a risk of falling 5 metres or more.

Erecting or dismantling scaffolding with a risk falling 5 metres or more.

Work in any pit, shaft, trench, or other excavation in which any person is required to work in a space more than 1.5 metres deep and having a depth greater than the horizontal width at the top.

Work in any drive, excavation, or heading in which any person is required to work with a ground cover overhead.

Work involving the use of explosives, or storage of explosives for use.

Work that in which a person breathes compressed air, or respiratory medium other than air.

Working with asbestos.

(3 marks)

(c) (i) Worksafe NZ


(1 mark)

(ii) 24 hours

(1 mark)

**Total 8 marks**

**ANSWER 10**



Vertical riser correct sizes (2 marks)  
 Each horizontal lateral correct (1 mark each)

**Total 10 marks**



## ANSWER 11

- (a) A preapproved method of construction or installation that will comply with the New Zealand Building Code. (2 marks)
- (b) A preapproved test or calculation to ensure an installation design will comply with the New Zealand Building Code. (2 marks)
- (c) A construction or installation method that has not been preapproved but that will meet the requirements of the New Zealand Building Code. (2 marks)

**Total 6 marks**

## SECTION B

1. E 45°
2. C 85 mm.
3. D 15 years.
4. B 342.
5. C 27
6. D 125
7. C 3.500 metres.
8. D 625 litres.
9. A In the event of a waste pipe blockage, dirty water from one sink could contaminate clean water in the other.
10. A When the discharge from connected fixtures is expected to be foamy.
11. A 1200 mm.
12. B The sum of the unit ratings of the fixtures discharging into the floor waste gully.
13. D 7
14. E Tundish.
15. A 3 kPa.
16. C 3 minutes stabilisation followed by a 2 minute test.

**Total 16 marks**